

# City of Alhambra



*Gateway  
to the  
San Gabriel Valley*

*111  
South First Street  
Alhambra  
California  
91801*

## **ADDENDUM NO. 1**

### **RFP 2M23-51 PROFESSIONAL DESIGN SERVICES FOR THE CITYWIDE BUS STOP IMPROVEMENTS PROJECT**

**MAY 30, 2023**

### **NOTICE TO ALL**

The following clarifications are issued for the proposed project:

1. Revised Item 5 on Bid Schedule page C-3
2. Revised Item 6 on Bid Schedule page C-3
3. Revised Item 8 on Bid Schedule page C-3
4. Bid Opening Date Change: **June 15, 2023.**

Issued by:

Melissa Ramos  
Deputy Director of Public Works  
City of Alhambra Public Works

**Bid Schedule for 2023 POLICE DEPARTMENT ROOFING IMPROVEMENTS PROJECT  
N2M23-51  
Contractor to Verify all Measurements and Quantities.**

Item #	Description	Quantity	Unit	Unit Price	Total Price
4	Furnish and Apply 230 Polyurethane Foam Per Manufacturer's Recommendations. Roofing Foam is to be a minimum 1.5 inches thick. Fill any low areas with additional foam. Taper all foam to all drains and scuppers.	29,000	SF	\$ _____	\$ _____
5	Furnish and Apply Grey Base Coat Per Manufacturer's Recommendations Acrylic shall be a minimum <b>16</b> Dry mills.	29,000	SF	\$ _____	\$ _____
6	Furnish and Apply White Top Coat Per Manufacturer's Recommendations Acrylic shall be a minimum <b>16</b> Dry mills	29,000	SF		
7	Furnish and Apply White Roofing Granules in Wet Topcoat Per Required Specification.	29,000	SF	\$ _____	\$ _____
8	Ten Year <b>Manufacturer</b> Warranty On Material And Labor. General Coating's specialist must be contacted prior to start and completion of work.	1	LS	\$ _____	\$ _____
<b>Quote amount in Writing:</b> _____					\$ _____